# Commercial Proposal & Quotation – Rooftop Solar PV System

*Turnkey EPC supply, installation and commissioning · 185.4 kWp grid-tied · zero export · no battery*

| | | | |
|---|---|---|---|
| **Quotation No.:** | Q-KMH-PV-2026-001 | **Date:** | 05-11-2026 |
| **Revision:** | A | **Valid until:** | 05-12-2026 (30 days) |

## 1. Project Details

| | |
|---|---|
| **Project name:** | Kampala Marriott Hotel – 185.4 kWp Rooftop Solar PV (mezzanine roof) |
| **System:** | Grid-tied solar PV, self-consumption, zero-export control, no battery storage |
| **Location:** | Kampala, Uganda · 0°18'11.34"N, 32°35'13.76"E · Ref. drawing D18102-DD-A-104 |

## 2. Client & Supplier Details

| | | | |
|---|---|---|---|
| **Client:** | Kampala Marriott Hotel | **Supplier:** | Tororo PV Power Company Ltd. |
| **Address:** | Kampala, Uganda | **Address:** | Aha Tower, 4th Floor, Lourdel Road, Nakasero, Kampala |
| **Contact:** | | **Contact:** | Mr. Mahil |
| **Mobile / Email:** | | **Mobile / Email:** | +94 773 55 96 82 · mahil@windforce.lk |

## 3. Quotation (Turnkey EPC)

| No. | Scope of supply & works | Qty | Unit | Total Price (USD) |
|---|---|---|---|---|
| 1 | PV modules – 620 Wp bifacial N-type TOPCon (Tier-1) | 299 | nos | **USD 121,115** |
| 2 | String inverters – 80 kW, 1100 V, multi-MPPT | 2 | nos | |
| 3 | Ballasted aluminium mounting structure, 10° tilt | 1 | lot | |
| 4 | DC system – PV cable, connectors, string isolators, cable tray | 1 | lot | |
| 5 | AC system – AC combiner panel, MCCBs, cabling to main LV switchboard | 1 | lot | |
| 6 | Smart data logger, remote monitoring & zero-export control | 1 | set | |
| 7 | Earthing & lightning protection integration | 1 | lot | |
| 8 | Installation, testing & commissioning | 1 | lot | |
| 9 | Transport, logistics & customs clearing to site | 1 | lot | |
| | **TOTAL TURNKEY EPC PRICE (excluding VAT and other applicable taxes)** | | | **USD 121,115** |

*Equivalent to USD 0.65 per Wp · Amount in words: One hundred twenty-one thousand one hundred fifteen US Dollars only.*

## 4. Expected Performance & Savings (indicative)

| | | | |
|---|---|---|---|
| **Year-1 generation:** | 274,362 kWh (≈ 22,900 kWh/month) | **Year-1 savings:** | USD 19,212 (at USD 0.070/kWh) |
| **Simple payback:** | ≈ 6.1 years | **Project IRR (25 yrs):** | 16.6 % |
| **NPV @ 10 % (25 yrs):** | USD 71,221 | **25-yr net savings:** | USD 569,043 |
| **Cost of solar energy:** | USD 0.052/kWh (LCOE) | **Self-consumption:** | 100 % used on site |

## 5. Payment & Commercial Terms

| | |
|---|---|
| **Price basis:** | Turnkey EPC, delivered, installed and commissioned at site, Kampala. Currency: USD. |
| **Payment terms:** | 30 % advance with purchase order · 60 % on delivery of main equipment to site · 10 % on commissioning |
| **Taxes:** | Prices exclude VAT, withholding tax and any other statutory levies, which shall be charged as applicable. |

## 6. Delivery & Project Schedule

| | |
|---|---|
| **Programme:** | Equipment delivery 8–10 weeks from PO and advance payment; installation and commissioning ≈ 4 weeks after delivery (≈ 12–14 weeks in total). |

## 7. Warranties

| | | | |
|---|---|---|---|
| **PV modules:** | 12-yr product · 30-yr linear power | **Inverters:** | 5 years (extendable) |
| **Mounting structure:** | 10 years | **Workmanship:** | 2 years from commissioning |

## 8. Notes & Exclusions

1. Final quantities are subject to detailed engineering and site survey; price will be adjusted for any change in scope.
2. Excluded: roof structural strengthening or waterproofing works, battery storage, utility/permit fees, and works not listed above.
3. Client to provide roof access, a spare 250 A way on the main LV switchboard, and power/water during installation.
4. Savings figures are estimates based on the stated tariff and typical Kampala irradiation; actual results may vary.

**For Tororo PV Power Company Ltd.**

Signature / Name / Date: _____

**Accepted by Client (Kampala Marriott Hotel)**

Signature / Name / Date: _____