
## PLAN – PV LAYOUT, INVERTERS & ACCP ON MEZZANINE ROOF (ENERACK BALLAST, 10° TILT)




**INVERTER STATION (steel frame + canopy)**

DCI-01/02 DC isolator units (8 × 2P 1200 V 32 A each)

DCS-01/02 DC SPD units (8 × Type 2, 1100 V each)


INV-01/02 Sigen PV 80M1 80 kW · ACCP 400 A

C3 4C×240 mm² Al XLPE/SWA


to MLVS via riser

(≈ 200 m, armour = PE, route TBC)

### SECTION A – 2P TABLE (2 × 23 modules)




### SECTION B – 1P TABLE (1 × 23 modules)




### TABLE SCHEDULE

| Table | Type | Modules | Inverter |
|---|---|---|---|
| T1, T2 | 2P × 23 | 92 | INV-01 |
| T3 | 1P × 23 | 23 | INV-01 |
| T4 | 2P × 23 | 46 | INV-01: 37 · INV-02: 9 |
| T5–T7 | 2P × 23 | 138 | INV-02 |
| **TOTAL (77 frames, 26 rail lines)** | | **299** | **INV-01 152 · INV-02 147** |

### DESIGN DATA

| | |
|---|---|
| Module | 620 Wp bifacial TOPCon, 2382 × 1134 × 30 mm |
| Structure | Enerack ballast, dwg EPJ-26110401 V1.0 |
| Tilt / wind / snow | 10° / 35 m/s / 0 kN/m² |
| Rails | R80, 8 × 3000 + 2630 = 26,630 mm per line |
| Frames | 11 per table: first at 315, then 10 × 2,600 |
| Spacing | 20 mm module gap · 800 mm aisle · ≥ 950 mm rail to wall |

### LEGEND

INV-01 modules · INV-02 modules · Inverter · ACCP · DC isolator unit · DC SPD unit

DC cable tray · C3 + E3 to LV room · Existing ducts

Rail · Frame / post · Foot block (300 × 300 indicative)

Setback line · Obstruction

NOTES: 1. Dimensions in mm. 2. Roof outline traced from D18102-DD-A-104; verify on site. 3. Foot block size and ballast weight per Enerack calculation; roof load to be approved by the building structural engineer. 4. All tables lie within the architect's solar zone. 5. Inverter station and duct positions indicative – confirm on site with the hotel; C3 riser route and LV room location TBC.

## ROOFTOP SOLAR PV LAYOUT

| | |
|---|---|
| Project | Marriott Hotel – Mezzanine Roof |
| Client | Kampala Marriott Hotel |
| Drawing No. | PV-LAY-D18102-002 Rev C |
| Date / Scale | 9 November 2026 · NTS (A3) |